REQUEST FOR PREQUALIFICATION

Guilford County Schools

NEW HUNTER ELEMENTARY SCHOOL
GREENSBORO, NORTH CAROLINA
JUNE 2015

boomerang

HUNTER ELEMENTARY SCHOOL

ATTENTION CONTRACTORS

Metcon, Inc., & WC Construction are soliciting first-tier contractors to submit pre-qualifications for Hunter Elementary Replacement School, Greensboro, NC. Second-tier subcontractors are urged to submit information about their firm and their interest in participating in the project.

Completed prequalification forms are due August 14, 2015, and a final prequalified list will be available on or before August 20, 2015.

Bidders must be pre-qualified in order to bid. Prequalification forms, information and bid package descriptions are available online at: http://metconus.com/estimating/cm-risk/GCSHunter or by contacting Rhonda Deese, (910)521-8013, via email – rdeese@metconus.com.

Metcon|WC Construction, LAC Consulting Group and Guilford County Schools encourage participation by all qualified subcontractors. HUB and minority contractors are encouraged to participate.

Plans and forms will be available online at the same address above and print copies available at other locations. Pre-Bid meetings will be held July 15, 2015 and August 5, 2015, at noon in the school's media center.

Guilford County Schools

Project Details

New Hunter Elementary will be located at the existing property at 1305 Merritt Drive, Greensboro, NC, behind the existing school on the current track and playfield areas. Upon completion of the new school and parking areas, the existing school will be abated and demolished. Foundations are continuous concrete strip footings and isolated spread footings for columns and any structural steel frame. Large assembly areas will have reinforced masonry walls. The roof assembly is a combination of a small amount of metal wall and roof panels and 2-ply SBS Modified Bitumen Roofing. Exterior load-bearing and interior walls are mostly masonry with some gypsum board in various configurations. Aluminum framed entrances, storefronts, and windows, tubular sky lighting, standard hollow metal doors & hardware, vinyl composite tile, tile carpet, ceramic tile, and specialty flooring in the gym and stage areas, sound attenuation panels, stage curtains, gym equipment, kitchen equipment, comprise the interior.

Complete and Return

Company Information:

Company Name: _____

Phone: _____

Fax: _____

Email: _____

Submitting Prequalification Statement:

☐ **Yes** ☐ **No**

METCON |WC CONSTRUCTION, LLC *A JOINT VENTURE*

ADVERTISEMENT FOR PREQUALIFICATION STATEMENTS