

Demolition of Stratford Arms Apartments-Greenville, N.C.

Addendum #1

The following information is provided as an addendum to the project per site visit conducted on Wednesday, March 28, 2012 @ 2:00 PM

1. Soil Compaction:

1. Do not deposit any fill on sub grade that is muddy. Remove all material not suitable for compaction.
2. Fill shall be place and compacted in successive layers not exceeding eight (8) inches until the proper sub grade is reached. It shall be the Contractor's responsibility to correct any depressions that occur as a result of improper compaction.
3. If necessary, soil shall be moistened or allowed to dry to correct moisture content before compaction.

2. Contents of the buildings: All buildings/units may contain appliances to include refrigerators and stoves. An estimated 10% of the units may contain furniture.