

## Request for Quotation

Date 11/3/2014

From: Charlotte Mecklenburg Schools Building Services

Project Mgr. Steve Carpenter, Facilities Engineer, 980-429-0683

Location: McKee Rd. ES 4101 McKee Rd. Charlotte, NC 28270

Project: Remove and replace all HVAC mechanical pipe insulation, exposed and above ceiling in the building.

### Scope of Work:

- Supply permits and inspections if required by Mecklenburg County.
- Remove and discard all existing insulation to be replaced.
- Supply and install minimum 1" armaflex insulation to all mechanical piping above ceiling, and on exposed piping.
- Install PVC jacket on all exposed piping.
- Provide all labor, glues, tapes, and jacketing for completed project.
- Repair and/or add any damaged/missing pipe hangers if needed.
- Replace and or repair any damaged sheetrock disturbed for this project.
- Clean up any spills or messes made during the installation project.
- Remove and reinstall any ceiling tile to complete project, care must be considered during this process, report any damaged tile to project mgr. asap.
- If awarded bid, provide Certificate of Liability Insurance with the Charlotte Mecklenburg Board of Education as Additional Insured and Certificate holder section reading as follows;  
The Charlotte Mecklenburg Board of Education  
P.O. Box30035 (No Attn. Line )  
Charlotte N.C. 28230-0035
- The owner reserves the right to reject any bid, to waive informalities, and to award contracts to other than the low bidder should it be deemed in their best interest.

- All bids are due by noon 11/20/2014