

MULTIPURPOSE BUILDING
(DCC # 467)

LENOIR COMMUNITY COLLEGE

KINSTON, NORTH CAROLINA

15 APRIL 1988

ARCHITECT

JOHN HICKMAN ARCHITECT P.A.
KINSTON, N.C.
919 - 527 - 4112

MECH. & ELEC. ENGINEER
JEFFRIES & ASSOCIATES
RALEIGH, N.C.
919 - 872 - 7580

STRUCTURAL ENGINEER
LASATER-HOPKINS
RALEIGH, N.C.
919 - 832 - 5587

LCC:
NURSING
BUILDING

SCHEDULE OF DRAWINGS


A-1	SITE PLAN
A-2	SITE DETAILS
A-3	FIRST FLOOR PLAN & DETAILS
A-4	SECOND FLOOR PLAN & DETAILS
A-5	REFLECTED CEILING PLAN
A-6	ROOF PLAN & DETAILS
A-7	EXTERIOR ELEVATIONS & WINDOW DETAILS
A-8	BUILDING SECTIONS & DETAILS
A-9	WALL SECTION & DETAILS
A-10	WALL SECTION & DETAILS
A-11	DOOR SCHEDULE & DETAILS
A-12	ROOM & FINISH SCHEDULE & DETAILS
A-13	SECTION THRU EXTERIOR STAIR
U-1	UTILITY SITE PLAN
S-1	FOUNDATION PLAN
S-2	SECOND FLOOR FRAMING PLAN & DETAILS

S-3	ROOF FRAMING PLAN & DETAILS
S-4	RETAINING WALL DETAILS & STAIR DETAILS
S-5	GENERAL NOTES & DETAILS
P-1	PLUMBING PLAN - FIRST FLOOR
P-2	PLUMBING PLAN - SECOND FLOOR
P-3	PLUMBING SCHEDULES & NOTES
M-1	MECHANICAL PLAN - FIRST FLOOR
M-2	MECHANICAL PLAN - SECOND FLOOR
M-3	MECHANICAL SCHEDULES & NOTES
E-1	POWER PLAN - FIRST FLOOR
E-2	LIGHTING PLAN - FIRST FLOOR
E-3	POWER PLAN - SECOND FLOOR
E-4	LIGHTING PLAN - SECOND FLOOR
E-5	ELECTRICAL SCHEDULES & DETAILS

BUILDING DATA

ITEM	AMOUNT
SQ. FT. FLOOR	141,065 sq. ft.
CUBICAL CONTENT	199,305 cu. ft.
ROOF DECK "U" FACTOR	.048
HEATING - MBH	138
AIR CONDITIONING - TONS	28.25
FIXTURE UNITS - WATER	233
FIXTURE UNITS - WASTE	131
WATER DEMAND - GPM	97
ELECTRICAL LOAD - KW	208.8
R-FACTOR (WALL)	19.55
TYPE IV PROTECTED	

DRAWING LEGEND

	BRICK		DOOR SYMBOL
	MASONRY BLOCK		WINDOW SYMBOL
	CONCRETE		WATER CLOSET
	STUD WALL		LAVATORY
	FINISH WOOD		PAPER TOWEL DISPENSER
	ROUGH WOOD		SOAP DISPENSER
	INSULATION		METAL AS NOTED
	RIGID INSULATION		DETAIL NUMBER DETAIL REFERENCE SHEET NUMBER
	STEEL		ROOM NUMBER

AREA MAP

