

TOWN OF WAYNESVILLE

REBID ADDENDUM #1

for
**PIGEON STREET WATER REPLACEMENT
PROJECT**

Project # 23001

Prepared for
The Town of Waynesville
Public Services Department
By
Mattern & Craig

The Town of Waynesville has created this REBID Addendum (#1) in order to make changes to the Bid Form for the Pigeon Street Water Replacement Project and to answer questions received from potential bidders. In order to submit a responsive bid, the bidder must use the Bid Form included in this REBID Addendum #1 to replace the Bid Form in the REBID contract documents.

Potential bidder questions:

1. Was there any Addendums from the first bid? *(Answer) Yes, but the Addendum from the first bid has been incorporated into the REBID contract.*
2. I don't see a Concrete item in the bid sheet. Several of the meters are in the sidewalk. Also, it appears that possibly some Curb and Gutter may need to be removed and repoured for at least one water tie in. Will this be incidental to these items or will a separate pay item be issued? *(Answer) All concrete work necessary to reconnect water meters will be incidental to the work. No additional payment will be made for any concrete work not specifically called out in the contract as a pay item.*
3. On the 10 service reconnects do we have to tie into the front of the existing meter or replace the entire meter assembly and tie in the private side service line behind the meter? *(Answer) The Town of Waynesville will supply the contractor with new water meters to be installed at all reconnections.*
4. Are we to assume there will be no rock in the water/sewer trenches on the project? Can a rock excavation unit price be added? *(Answer) This Addendum includes a new bid form that adds a line item for Rock Excavation. Please see the included Project Special Provisions for details concerning this new line item.*

PROJECT SPECIAL PROVISIONS

Line 23 Rock Excavation

Remove rock that is encountered during excavation for the installation of water and sewer lines and their appurtenances. Areas of Rock Excavation must be identified before removal and approved by Jeff Stines, Ricky Foster, or the Town of Waynesville's appointed representative. Payment for Rock Excavation will be by the Cubic Yard of rock removed.

Pigeon Street Water Replacement Project BID FORM						
LINE	DIVISION/ SECTION	DESCRIPTION	QTY.	UNIT	UNIT PRICE	AMOUNT
1	8/800	Mobilization	1	L.S.		
2	11/All	Traffic Control	1	L.S.		
3	16/All	Erosion Control	1	L.S.		
4	6/654	Asphalt Surface Course S9.5C	150	Tons		
5	6/654	Asphalt Base Course I19.0C	230	Tons		
6	5/520	ABC Stone	400	Tons		
7	15/1510	6" DIP, PC 350 Water Line	1,500	L.F.		
8	15/1515	6" Valve	14	EA.		
9	15/1515	6" Tapping Sleeve and Valve	1	EA.		
10	15/1515	Reconnect Water Meter	10	EA.		
11	15/1515	Fire Hydrant	3	EA.		
12	15/1515	Fire Hydrant Leg	90	L.F.		
13	15/1515	Water Service Line	160	L.F.		
14	15/1515	Ductile Iron Water Pipe Fittings	1,450	LB.		
15	15/1530	Abandon 6" Water Line	1,400	L.F.		
16	15/1530	Remove Fire Hydrant	3	EA.		
17	15/1525	4' Diameter Utility Manhole	3	EA.		
18	15/1525	Utility Manhole Wall 4' Diameter	8	L.F.		
19	15/1530.	Remove Utility Manhole	3	EA.		
20	15/1520	Sewer Service Line	80	L.F.		
21	15/1530	Abandon 8" Sewer Line	410	L.F.		
22	15/1520	8" DIP, PC 350	400	L.F.		
23	Addendum 1	Rock Excavation	50	C.Y.		

TOTAL _____

Contractor: _____

Address: _____

Federal ID Number: _____

License #: _____

Authorized Agent: _____

Title: _____

Signature: _____

Date: _____

Witness: _____

Title: _____

Signature: _____

Date: _____

Failure to have knowledge of this Addendum does not release the Contractor from conforming to its requirements.

THIS ADDENDUM IS NOW PART OF THE REBID DOCUMENTS
FOR PROJECT#23001
PIGEON STREET WATER REPLACEMENT PROJECT